D.A.V. PUBLIC SCHOOL, JR. BRANCH, ASHOK TOWN HALL ROAD, JAMUI, BIHAR

PH-06345-224272; MOB-9431468660; E-MAIL-dav_jamui@rediffmail.com

REF:-DAV-JM/SB/MR/01/25-26

BILL OF QUANTITY

Date:- 19 DEC. 2025

	MISCEL	LANEOUS REPAIR WORK FOR D.A.V. PUBLIC SCHOOL, SE	R. BRANCH,	JAMUI,	BIHAR.	
SI.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
	(1) MISC	ELLANEOUS REPAIR WORKS			-	
1	9.101	Providing and fixing alluminium hanging floor door				
		stopper,ISI marked,anodised (anodic coating not less				
		than grade AC 10 as per IS 1868) transparent or dyed				
		to required colour and shade with necessary screws				
		etc. complete.				
	9.101.2	Twin rubber stopper.	65	No.		
2	14.5	Renewing glass panes, with putty and nails wherever				
		necessary including racking out the old putty:				
	14.5.1	Float glass panes of thickness 4mm	11.90	Sqm		
3	9.5.2.2	Providing and fixing 30mm thick Kiln seasoned				
		and chemically treated hollock wood paneled or				
		paneled and glazed shutters for doors, windows,				
		and clear story windows including ISI marked M.S.				
		pressed butt hinges bright finished of required size				
		with necessary screws excluding panelling which				
		will be paid for separetely,all complete as per	23.42	Sqm		
		direction of Engineer-in-charge.				
		Note:-Alluminium sheet coating on inner surface				
		of toilet door upto 4'-0" height shall be provided.				
4	10.5	Providing and fixing 1 mm thick M.S. sheet door with				
		frame of 40x40x6 mm angle iron and 3mm MS gusset				
		plates at the junction and cameras all necessary				
		fittings complete including applying a priming coat of				
		approved steel primer.				
	10.5.2	Using flats 30x6 mm for diagonal braces and central				
		cross pices.	1.63	Sqm		
5	9.57	Providing and fixing ISI marked oxidised M.S. pressed				
		butt hinges with necessary screws etc. complete.				
	9.57.1	125x65x2.12 mm	8.00	Each		
6	14.85	Taking out existing wooden door shutter, repair by				
		cutting painting etc. and refixing of repaired door				
		shutter to existing door frames, including replacement				
		of hinges with screws etc. as required, all complete as				
		per the direction of the Engineer-in-charge.	8.00	Each		
7	11.38	Providing and laying Ceramic glazed floor tiles 300x				
		300 mm (thickness to be specified by the manufact-				

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		urer) of first quality conforming to IS:15622 of appro-				
		ved make in colours such shades except white, Ivory				
		Grey,Fume Red,Brown laid on 20 mm thick cement				
		mortar 1:4(1 cement: 4 coarse sand)including pointing				
		the joints with white cement and matching pigment				
		etc. complete.	9.29	Sqm		
8	11.36	Providing and fixing first quality ceramic glazed				
		wall tiles confirming to IS 15622(Thickness to be				
		specified by manufacturer) of approved make in				
		all colours, shades execpt burgundy, bottle green,				
		black of any size as approved by engineer in				
		charge in skirting, risers of steps and dados over				
		12mm thick bed of cement mortor 1:3 (1 cement,				
		3 coarse sand) and jointed with grey				
		cement slurry @ 3.3 Kg/sqm including pointing				
		in white cement mixed with pigment of matching				
		shade complete.	17.66	Sam		
9	11.23	Marble stone flooring with 18 mm thick marble				
		stone (sample of marble shall be approved by				
		Engineer-in-charge) over 20 mm (average) thick				
		base of cement mortar 1:4 (1 cement: 4 coarse sand)				
		laid and jointed with grey cement slurry including				
		rubbing and polishing complete with:				
	11.23.2	Rajnagar plain white marble 18 mm thick above 0.10				
	11.20.2	sqm upto 0.20 sqm	12.73	Sam		
10	18 49	Providing and fixing C.P. brass bib cock of approved	1 22.75	94		
	10.13	quality confirming to IS:8931	103	Each		
11	14.80	Providing and fixing white vitreous china water closet	103	Lucii		
	100	squatting pan (Indian type) along with "S" or "P" trap				
ı		including dismantling of old WC seat and "S" or "P"				
		trap at site complete with all operations including all				
		necessary materials, labour and disposal of dismantled				
		material i.e. malba, all complete as per the direction				
		of Engineer-in-charge.				
	14.80.2	Orissa pattern W.C. pan of size 580x440 mm	2	Each		
12	<u> </u>	Providing and fixing wash basin with C.I. brackets	-	Lucii		
		15 mm C.P. brass pillar taps, 32 mm C.P. brass waste				
		of standard pattern including painting of fittings and				
		brackets, cutting and making good the walls				
		wherever required:				
	17.7.7	White Vitreous china Flat back wash basin size 450x				
	1 / . / . /		,	Each		
13	17 22	300 mm with single 15 mm C.P. brass pillar tap.	 	Eacli		
13	17.23	Providing and fixing white vitreous china flat back or				
		wall corner type lipped front urinal basin of 430x260x	1	Each		
		50 mm or 340x410x265 mm sizes respectively.	1 3	Each		

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
14	17.19	Providing and fixing controlled flush, low level cistern				
		made of vitreous china with all fittings complete.				
	17.19.1	10 litre (full flush) capacity- white	2	Each		
15	17.28	Providing and fixing P.V.C. waste pipe for sink or wash				
		basin including P.V.C. waste fittings complete.				
	17.28.2	Flexible pipe				
	17.28.2.2	40 mm dia	10	Each		
16	18.18	Providing and fixing ball valve (brass) of approved				
		quality, high or low pressure, with plastic floats				
		complete.				
	18.18.1	15 mm nominal bore	21	Each		
17	MR	Miscellaneous expences during renovation, dismantli-				
		ng, controll of seepage of bath rooms etc. complete as				
		per direction of Engineer-in-Charge.	LS			
3		305,404- leakage	LS			
)		404 Wall dampness	LS			
		SUB TOTAL				
18		Add extra for external and internal PHE work,				
		external and internal electrical works,roof treatment				
3		Switch board repairing	3	No.		
)		Switches(6 amp)	25	No.		
2		Fuse repair	2	No.		
t		Board repair	4	No.		
9		3 Pin shoket	6	No.		
f		Switch(16 amp)	2	No.		
g		Full repair of top floor drain pipe	LS			
		TOTAL				
		ROUNDING OFF				